



# The County

PRINCE EDWARD COUNTY ♦ ONTARIO

## PRINCE EDWARD COUNTY ADDENDUM No. 3

**Date:** Friday, January 26, 2018  
**Contract:** 2017-EDW-76  
**PICTON HEIGHTS RESERVOIR WATERMAIN IMPROVEMENTS  
AND ILLUMINATED SIDEWALK**

---

### I. DIRECTIVE

This Addendum shall form an integral part of the plans and specifications for the above-mentioned project and shall be read in conjunction therewith. This Addendum shall, however, take precedence over all requirements of the previously issued drawings, specifications, or addenda with which it may prove at variance, unless otherwise clarified by the Engineer.

### II. Part A – REVISIONS TO ADDENDUM NO. 2

1. II. Part A – Instructions to Bidders – Section 2 - Tender Delivery & Opening (*pg 3 of 42*)  
The NEW closing date and time for submitting tender has been extended from 2:00:00 p.m., Local Time, Tuesday, January 30, 2018 to 2:00:00 p.m., Local Time, **Tuesday, February 13, 2018.**
2. II. Part A – Instructions to Bidders – Section 5 - Inquiry (*pg 5 of 42*)  
The NEW closing date and time for submitting inquiries, in writing, has been extended from 4:00 p.m., Local Time, Tuesday, January 23, 2017 to 4:00 p.m., Local Time, **Friday, February 2, 2018.**
3. V. Revision to Drawings, Item 4. Drawing G107, Note “d.”  
Clarification:
  - All top coat HL3 quantity shall be paid under Special Provisions Items-Item No.18
  - Where there is a road reconstruction, the base coat (HL8) shall be paid under Special Provisions Items - Item No. 19.

- Where there is trench restoration instead of road reconstruction (Church Street and Union Street) the payment for base coat (HL8) shall be included in Special Provisions Items - Item Nos. 39 & 40

### III. Part A – INSTRUCTIONS TO BIDDERS

1. Part A – Instructions to Bidders – Section 27 – Bid Deposit (*pg 17 of 42*)  
Clarification: Either of Bid Bond, or Certified Cheque is acceptable as a Bid Deposit.

### IV. Part C – FORM OF TENDER

1. Part C – Form of Tender – Reference Information  
Delete blank page (*pg 35 of 42*) in its entirety.

### V. REVISIONS TO TERMS OF REFERENCE

1. Special Provisions – Items, Item No. 18 HMA – Top Coat HL3 & Item No. 19 Base Coat HL8  
Clarification: PG 58-28 to be used as typical asphalt.
2. Special Provisions – Items, Item No. 28 and 29 – Topsoil, Hydroseed, and Sod  
Clarification:
  - a) Use Salt Tolerant Mix – Canada #1 Ground Cover Mixture for hydroseed mix as per reference OPSS 804
  - b) Use 150 mm for topsoil thickness as per reference OPSS 802.
  - c) Use Kentucky Bluegrass/Fine Fescue for the type of SOD as per reference OPSS 803
3. Special Provisions – Items, Item No. 45, 46, 47, 48, & 49 – Gate Valve & Gate Boxes  
Add Note: The approved valve manufacturer is Clow, or approved equivalent.
4. Special Provisions – Items, Item No. 52 – Valve Box Removal  
Add Note: “Remove the valve boxes to below the road surface for the areas that have reconstruction/resurfacing of the asphalt road. The General Contractor is responsible for noting on the as-builts, complete with GPS coordinates the location and depth of the removed valve box and the location of the abandoned watermain”.
5. Special Provisions – Items, Item No. E13 – Supply and Install Concrete Poles  
Delete statement “Standard drawings: OPSD-2200.020, 2220.01, 2255.020” and replace with “Standard drawings: OPSD-2200.020, 2220.01, 2255.020, and 2225.010”

### VI. REVISIONS TO DRAWINGS

1. Drawing G101
  - a. Clarification: At the top left corner of the plan view, outside of the fenced reservoir enclosure, to the right top corner of an existing buried chamber, add note "New exterior actuator for one of the valves in this chamber - similar to the new exterior actuator at the connection chamber in Detail 1. This is a provisional item."

- b. For the existing buried chamber between the Picton Heights Reservoir and the Existing Booster Station, add note "New exterior actuator for the gate valve as shown in Detail 1. This is a provisional item."
2. Drawings G105
    - a. Delete note "Existing water service to Macauley Heritage Building to be replaced with new service c/w new curb stop. Exact location of existing service is unknown" and replace with the following:  
"Existing ¾" copper water service to Macauley Heritage Building to be replaced with new service c/w new curb stop, similar to existing. Exact location of existing service is unknown. Contractor to field verify. Provide a second new ¾" copper water service line coming off of the new service line (ahead of its new curb stop), complete with a separate curb stop – shut off valve and stand. Connect to this second water service line a new Boshart Industries self-draining hydrant. Location of the sample hydrant to be coordinated with County Operations."
3. Drawings G104, G105, and G106
    - a. Clarification: The existing watermain shown on Old Church St., Church St. and Union St. shall be filled with grout and abandoned after commissioning of new watermain, and connection of new watermain to the existing watermains on the side streets, as referenced in the note on the drawings G104 and G105.
4. Drawing E01
    - a. In Table, Summary of Lighting Pole Assemblies, in Notes column for Pole P1 to P10, add Note "OPSD 2225.010".